

# **REVIEW EXERCISE**

# EARNED VALUE MANAGEMENT

### **GENERAL OBJECTIVE**

• Review the earned value management (EVM) tools and techniques by solving an exercise.

### CASE DESCRIPTION

The construction of a new highway includes the earth movement, the trace, the pavement, the signaling, and the construction of ten bridges.

Four work areas were defined (Sector 1, Sector 2, Sector 3, and Bridges). Technically speaking the most difficult sector is Sector 2, since there are still some properties that haven't yet been expropriated and this will delay the initiation of the work in this sector.

The network diagrams for Sectors 1 and 3 have some slack/float, while Sector 2 and Bridges are part of the schedule critical path.

The total budget has been estimated at \$45,000,000.00 and the total time/schedule at 33 months.

Based on the following data, analyze the earned value at the end of the project's second trimester.



Universidad para la Cooperación Internacional

### Planned Value (PV)

DESCRIPTION	TRIMESTER 1	TRIMESTER 2	TRIMESTER 3	TRIMESTER 4	TRIMESTER 5	TRIMESTER 6	TRIMESTER 7	TRIMESTER 8	TRIMESTER 9	TRIMESTER 10	TRIMESTER 11
SECTOR 1											
Earth movement	\$200.000	\$300.000									
Trace	\$180.000	\$90.000									
Subbase		\$100.000	\$150.000	\$50.000							
Base			\$200.000	\$300.000	\$100.000						
Pavement					\$400.000	\$600.000	\$300.000				
Signaling						\$90.000	\$110.000				
SECTOR 2											
Expropriations	\$50.000	\$50.000									
Earth movement			\$400.000	\$500.000	\$600.000						
Trace			\$300.000	\$400.000	\$450.000						
Subbase				\$220.000	\$350.000	\$400.000	\$200.000				
Base					\$440.000	\$700.000	\$800.000	\$400.000			
Pavement							\$880.000	\$1.400.000	\$1.600.000	\$800.000	\$200.000
Signaling								\$200.000	\$350.000	\$150.000	\$50.000
SECTOR 3											
Earth movement	\$250.000	\$300.000									
Trace	\$200.000	\$120.000									
Subbase		\$120.000	\$180.000	\$50.000							
Base			\$240.000	\$360.000	\$100.000						
Pavement					\$480.000	\$760.000	\$200.000				
Signaling						\$50.000	\$100.000	\$30.000			
Bridges											
Design	\$200.000	\$200.000	\$200.000	\$400.000							
Construction				\$1.000.000	\$5.000.000	\$3.000.000	\$3.000.000	\$3.000.000	\$4.000.000	\$3.000.000	\$2.000.000
Signaling					\$300.000	\$400.000	\$200.000	\$150.000	\$150.000	\$100.000	\$100.000

### Actual Cost (AC)

DESCRIPTION	TRIMESTER 1	TRIMESTER 2	TRIMESTER 3	TRIMESTER 4	TRIMESTER 5	TRIMESTER 6	TRIMESTER 7	TRIMESTER 8	TRIMESTER 9	TRIMESTER 10	TRIMESTER 11
SECTOR 1											
Earth movement	\$170.000	\$290.000									
Trace	\$185.000	\$80.000									
Subbase		\$90.000									
Base											
Pavement											
Signaling											
SECTOR 2											
Expropriations	\$50.000	\$50.000									
Earth movement											
Trace											
Subbase											
Base											
Pavement											
Signaling											
SECTOR 3											
Earth movement	\$240.000	\$305.000									
Trace	\$210.000	\$100.000									
Subbase		\$115.000									
Base											
Pavement											
Signaling											
Bridges											
Design	\$200.000	\$200.000									
Construction											
Signaling											

### Earned Value (EV)

1.STP				-	r.	i i				1		SIP		
Earned Value (EV)												T		
DESCRIPTION	TRIMESTER 1	TRIMESTER 2	TRIMESTER 3	TRIMESTER 4		STER 5	TRIMESTER 6	TRIMESTER 7	TRIMESTER 8	TRIMESTER 9	TRIMESTER 10	TRIMESTER 11		
SECTOR 1						-	and shirts	d bara	144			Contraction in the		
Earth movement	\$190.000	\$290.000	-			COO	peraci	on Inte	macior	121				
Trace	\$190.000	\$80.000		-							-	-		
Subbase	+=====	\$100.000						1						
Base	-  -	+			1			1			1	1		
Pavement														
Signaling														
SECTOR 2														
Expropriations	\$50.000	\$50.000												
Earth movement														
Trace														
Subbase														
Base														
Pavement														
Signaling														
SECTOR 3														
Earth movement	\$245.000	\$305.000												
Trace	\$200.000	\$120.000												
Subbase		\$120.000												
Base														
Pavement														
Signaling														
Bridges														
Design	\$200.000	\$200.000												
Construction														
Signaling														

#### **INSTRUCTIONS**

Based on the information presented, answer the following questions:

- 1. How likely is that the project will finish on time?
- 2. What is the CPI for the project?
- 3. What is the estimated duration for the project?
- 4. If you were the project manager would you commit to the estimated duration of the project as per the previous question? Explain.
- 5. Are there any activities for which you would not recommend the percent complete earned value measuring technique? Explain with an example of one of the activities from this project.
- 6. The project sponsor requests that the earned value technique only be applied to the critical path activities. Will it be possible to use this technique in that context? Mention one advantage and one disadvantage of applying this strategy.

#### **RULES AND CONSIDERATIONS**

- The document must be presented in a .doc format. If needed, in order to support the • calculations, you can submit additional files such as MSExcel. These files should be sent as a compressed file type (.zip or .rar). The file must be uploaded to the virtual campus in the specific location established for this purpose.
- The document must be a maximum of ten pages in length.
- Questions related to this deliverable should be channeled through the Inquiries forum.